



कोहलपुर नगरपालिका

# नगर कार्यपालिकाको कार्यालय

कोहलपुर, बाँके

लुम्बिनी प्रदेश, नेपाल

Google Plus Code



6M2Q+5V7 Kohalpur

प.सं.: २०८०/०८१

च.नं.:



योजना तथा अनुगमन उपशाखा

मिति: २०८१/०१/१६

## विषय: दरभाउपत्र पेश गर्ने सम्बन्धमा

श्री नगरपालिकामा सूचिदर्ता भएका/नभएका सबै फर्महरु।

उपर्युक्त सम्बन्धमा यस कोहलपुर नगरपालिका वडा नं. ३ मा आ.व २०८०/०८१ को वार्षिक स्विकृत कार्यक्रम अन्तर्गत बजेट पुस्तिका शिर्षक नं. २३२ बाट रु.५,०००००। ( पाँच लाख मात्र ) बजेट व्यवस्थापन भएकोले विष्णु अधिकारीको घर देखि न्यौपानेको घर सम्म सडक स्तरोन्नती (कालोपत्रे) कार्य गर्नको लागि संलग्न BOQ भरी तपशिल बमोजिमका कागजात सहित ७ (सात) दिन भित्र यस कार्यालयमा पेश गर्नुहुन जानकारीका लागि सबैमा दोस्रो पटक यो सूचना प्रकाशित गरिएको छ ।

### तपशिल

१. दररेट पेश गरेको निवेदन
२. आ.व. २०८०/०८१ को लागि फर्म र इजाजत पत्र नविकरण भएको प्रमाणपत्रको प्रतिलिपी।
३. मु.अ.करमा दर्ता भएको प्रमाणपत्रको प्रतिलिपी।
४. आ.व. ०७९/८० को कर चुक्ता प्रमाणपत्रको प्रतिलिपी ।

*[Handwritten signature]*

*[Handwritten signature]*

धोलकराज ढकाल  
प्रमुख प्रशासकीय अधिकृत  
धोलकराज ढकाल  
प्रमुख प्रशासकीय अधिकृत

Office of Municipal Executive  
Kohalpur Banke  
Lumbini Province, Nepal  
**Bill Of Quantity**



*(Handwritten Signature)*

धोलकराज ठकाल  
प्रमुख प्रशासक

FY - 2080/081


Name of Road:- Bishnu Adhikariko Ghar Dekhi Pashim Sadak Staronnani( Road Black Top).  
Project Site: Kohalpur Municipality- 03, Banke

S.N.	Description of works	Unit	Quantity	Rate, (NRs)		Amount (NRs)	Remarks
				In Figure	In Words		
A	<b>Pavement Works</b>						
1.0	Project Information Board. All complete.	Job	1.00				
2.0	Filling Works for Preparation Of Sub-grade all complete.	m3	22.50				
3.0	Scarifying the existing road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications	m2	244.00				
4.0	Providing, laying, spreading, watering, levelling and compaction of natural sand gravel subbase grading as per table 12.1 of standard specification lead upto 10m.	m3	12.20				
5.0	Providing, laying, spreading, watering, levelling and compaction of crusher run materials for base course lead upto 10m. (a) Machine works	m3	34.77				
6.0	Providing and spraying bituminous prime coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc. all complete before applying prime coat. (1301 .1302)	Ltr	213.50				

Name Of Firm's:  
Address:  
Representative:  
Form's Stamp:



Kohalpur Municipality  
Office of Municipal Executive  
Kohalpur Banke  
Lumbini Province, Nepal  
Bill Of Quantity


  
 धूलिकराज देकाल

FY : 2080/081

Name of Road:- Bishnu Adhikariko Ghar Dekhi Pashim Sadak Staronnani( Road Black Top).  
Project Site: Kohalpur Municipality- 03, Banke

S.N.	Description of works	Unit	Quantity	Rate, (NRs)		Amount (NRs)	Remarks
				In Figure	In Words		
<b>A</b>	<b>Pavement Works</b>						
7.0	Providing and spraying bituminous tack coat MC30/MC70 including cleaning the road surface using wire, brushes, broom etc all complete before applying tack coat (1301.1302)	Ltr	155.86				
8.0	Providing mixing, laying, compaction etc all complete of 30mm thick bitumenous Premix Carpet.	m3	6.41				
9.0	Providing and laying sand seal all complete as per directed by engineer.	m2	213.50				
10.0	Supplying and applying paint for Road marking including cleaning, watering, brooming etc. all complete (10cm. wide strip) b) More than two coats over new bitumin surface	Rm	61.00				
<b>Sub - Total (A)</b>							
<b>VAT @13%</b>							
<b>Grand-Total</b>							

Name Of Firm's:  
Address:  
Representative:  
Form's Stamp: